



पी0 एन0 जी0, राजकीय स्नातकोत्तर महाविद्यालय, रामनगर
नैनीताल (उत्तराखण्ड)

Email- principal_pngrmr@yahoo.co.in

Web add- www.gpgcramnagar.org

पत्रांक-762 / क्रीड़ा/निर्माण/2025-26

दिनांक-20.12.2025

कोटेशन सूचना

सत्र 2025-26 के लिए महाविद्यालय के क्रीड़ा विभाग के अन्तर्गत स्थापित बॉक्सिंग रिंग में टिन शेड के निर्माण कार्य हेतु पंजीकृत फर्मों से कोटेशन आमंत्रित किये जाते हैं। कार्य आदि के विवरण की जानकारी कार्यालय से किसी भी कार्य दिवस को प्रातः 10.00 बजे से सांय 4.00 बजे तक प्राप्त की जा सकती है।

अतः आप संलग्न निर्धारित प्रारूप के अनुसार सामग्री की आपूर्ति की आँक मूल्य दर दिनांक दिनांक-29.12.2025 के अपराह्न 4:00 बजे तक स्पीड पोस्ट द्वारा भेजने का कष्ट करें। निर्धारित तिथि के उपरान्त प्राप्त कोटेशनों पर विचार नहीं किया जायेगा। कोटेशनों को दिनांक 30.12.2025 के अपराह्न 2:00 बजे महाविद्यालय के कार्यालय में खोला जायेगा। कोटेशन खोलने के तिथि में अवकाश होने की स्थिति पर अगले कार्य दिवस में खोले जायेगे।

क्र० सं०	कार्य का नाम	दर प्राप्त करने की तिथि
01	बॉक्सिंग रिंग में टिन शेड के निर्माण का कार्य	29.12.2025

प्राचार्य

राजकीय स्नातकोत्तर महाविद्यालय
रामनगर, नैनीताल

प्रतिलिपि सूचनार्थ और वृहद प्रचारार्थ चस्पा करने हेतु-

1. डा0 दीपक खाती को उक्त सूचना वेबसाइट में अपलोड करने के संबंध में।
2. महाविद्यालय के सूचना पट्ट में।

प्राचार्य

राजकीय स्नातकोत्तर महाविद्यालय
रामनगर, नैनीताल

Name of work- Construction of **Tin Shade for Boxing Ring** in P.N.G. Govt. P.G. College, Ramnagar, Nainital (Uttarakhand)

Format

Sr No	Item of Work	Qty	Unit	Rate	Per	Amount
01.	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead up to 50 m and lift up to 1.5 m, as directed by Engineer-in charge. All kinds of soil	08.01	cu.m.		cu.m	
02.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering all work up to Plinth level: 1:3:6 (1 Cement: 3 manufacture sand derived from recycled concrete aggregate (RAC): 6 graded stone aggregate 40mm nominal size Recycled aggregate (RA)	03.13	cu.m.		cu.m.	
03.	Providing and making of structural steel work in built up tubular (Round, Square or rectangular hollow tubes etc) trusses etc. including cutting, hosting, fixing in position and applying a priming coat of approved steel primer. Including welding and bottled with special shaped washers etc. all as per standard design.	498.00	Kg.		Kg.	
04.	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on over lapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. (0.80 mm Thick with zinc coating not less than 275 gm/m ²)	89.02	Sq.m.		Sq.m	
05.	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia 4 mm	12.49	Sq.m.		Sq.m.	
06.	Providing and fixing of M.S. grill gate as required pattern in frame of double door gate with M.S. flat, square or round bars etc. including with priming coat by steel primer and fixing with nut bolts and welding etc.	60.00	Kg.		Kg.	
07.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: One or more coats on new work and painting of external grills, gates etc.	86.55	Sq.m		Sq.m	
Note-Including all the Taxes.			Total Amount=			
			Grand Total			

22